
R-400

1 **OF** 1



## NOTES:

- 1. CALL FOR CLEAR AND GRADE INSPECTION PRIOR TO BASE COURSE BEING PLACED.
  VERIFICATION OF ROCKERY HEIGHT, FOUNDATION MATERIAL, AND ROCK SIZE BY CITY
  CLEAR AND GRADE INSPECTOR IS REQUIRED.
- 2. 4" TO 6" QUARRY SPALLS SHOULD BE PLACED DIRECTLY FROM TRUCK OR OTHER SUITABLE CONTAINER IN ORDER TO MAINTAIN CLEAN BACKFILL.
- 3. SPALLS MAY NOT BE NEEDED AT BASE OF ROCKERY IF NATIVE FOUNDATION MATERIAL IS SUITABLE AS DETERMINED BY THE GEOTECHNICAL ENGINEER OR THE CITY CLEARING AND GRADING INSPECTOR.
- 4. OPENINGS CHINKED WITH QUARRY SPALLS.
- 5. IF ROCKERY HEIGHT EXCEEDS 4', IT MUST BE DESIGNED BY A PRACTICING GEOTECHNICAL/CIVIL ENGINEER LICENSED IN THE STATE OF WASHINGTON. NO ROCKERY SHALL BE GREATER THAN 7' IN HEIGHT UNLESS APPROVED BY CITY.
- 6. A ROCKERY GREATER THAN 4' IN HEIGHT AND ON PRIVATE PROPERTY SHALL REQUIRE A BUILDING PERMIT WITH A THIRD PARTY INSPECTION TO BE CONSTRUCTED.
- 7. FILTER FABRIC SHALL BE MIRAFI 140 N SERIES OR APPROVED EQUAL.
- 8. OUTLET OF PERFORATED PIPE TO BE DETERMINED BEFORE CONSTRUCTION.